BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18328/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Repairs and maintenance to existing borewells in ward no. 8, kodigehalli

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K S CHOWDAREDDY		
				In Figures		In Words
1	11	Lifting of Submersible pump set as per Soecification and direction etc complete as per specifications and directions of engineer in charge of the work	Each	840.0	9240.00	Rupees Eight Hundred Forty Only
2	11	Transportation of pumping machineries etc complete as per specifications and directions of engineer in charge of the work	Each	880.0	9680.00	Rupees Eight Hundred Eighty Only
3	11	Labour charges (over hauling) etc complete as per specifications and directions of engineer in charge of the work	Job	540.0	5940.00	Rupees Five Hundred Forty Only
4	5	A) Repairs to Motor: Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6 months. (Above 10 HP upto 20 HP add Rs.150/- for every ◆ HP) up to 10 HP etc complete as per specifications and directions of engineer in charge of the work	No.	3600.0	18000.00	Rupees Three Thousand Six Hundred Only
5	6	12.5 HP	No.	4650.0	27900.00	Rupees Four Thousand Six Hundred Fifty Only
6	11	Starter (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	5000.0	55000.00	Rupees Five Thousand Only
7	11	Rotor (with one year Guarantee) etc complete as per specifications and directions of engineer in charge of the work	No.	4600.0	50600.00	Rupees Four Thousand Six Hundred Only
8	11	Upper Flange etc complete as per specifications and directions of engineer in charge of the work	No.	340.0	3740.00	Rupees Three Hundred Forty Only
9	11	Lower Housing etc complete as per specifications and directions of engineer in charge of the work	No.	640.0	7040.00	Rupees Six Hundred Forty Only
10	11	Carbon Housing etc complete as per specifications and directions of engineer in charge of the work	No.	450.0	4950.00	Rupees Four Hundred Fifty Only
11	11	Thrust bearing block assembly complete with Segment bearing pad etc complete as per specifications and directions of engineer in charge of the work	No.	1100.0	12100.00	Rupees One Thousand One Hundred Only
12	11	Oil Seal etc complete as per specifications and directions of engineer in charge of the work	No.	120.0	1320.00	Rupees One Hundred Twenty Only
13	11	Oil Seal Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	140.0	1540.00	Rupees One Hundred Forty Only
14	165	Guide vane etc complete as per specifications and directions of engineer in charge of the work	No.	170.0	28050.00	Rupees One Hundred Seventy Only
15	165	Impeller Shell moulded with aluminium Bronze) etc complete as per specifications and directions of engineer in charge of the work	No.	420.0	69300.00	Rupees Four Hundred Twenty Only
16	11	Discharge outlet (D.O) Bearing D.O Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	440.0	4840.00	Rupees Four Hundred Forty Only
17	11	Steel Bush etc complete as per specifications and directions of engineer in charge of the work	No.	140.0	1540.00	Rupees One Hundred Forty Only
18	11	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) etc complete as per specifications and directions of engineer in charge of the work	No.	950.0	10450.00	Rupees Nine Hundred Fifty Only
19	11	Non – return valve (NRV) assembly complete with rubber 'O' Ring etc complete as per specifications and directions of engineer in charge of the work	No.	1200.0	13200.00	Rupees One Thousand Two Hundred Only
20	11	Cable Guard etc complete as per specifications and directions of engineer in charge of the work	No.	150.0	1650.00	Rupees One Hundred Fifty Only
21	11	Brass Filter etc complete as per specifications and directions of engineer in charge of the work	No.	250.0	2750.00	Rupees Two Hundred Fifty Only
22	11	Re-erection charges of pumping machineries including overhauling and pointing etc complete as per specifications and directions of engineer in charge of the work	Each	900.0	9900.00	Rupees Nine Hundred Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

30/3/16